PIPE PIG LAUNCHER

BY

JIMMY LEA P/L



INTRODUCTION

Pipeline systems are essential for transporting liquids and gases over long distances. However, maintaining pipeline efficiency and ensuring cleanliness is a complex task. This is where pigging systems come into play. A pig launcher is a crucial component of the pigging system, designed to introduce pipeline inspection gauges, commonly referred to as pigs, into the pipeline. These pigs perform various tasks such as cleaning, inspecting, and separating different products in the pipeline. This article aims to provide a comprehensive understanding of pig launchers, their design, components, operation, and importance in pipeline maintenance.

WHAT IS A PIG LAUNCHER?

A pig launcher is a pressurised vessel that allows a pig to be inserted into the pipeline without interrupting the flow of the medium. The pig moves along the pipeline, performing specific functions such as cleaning or inspecting for corrosion, cracks, or other defects. A pig launcher is typically installed at the starting point of the pigging process, while a pig receiver is placed at the endpoint where the pig is retrieved after completing its journey through the pipeline.

COMPONENTS OF PIG LAUNCHER

A pig launcher consists of several essential components, each playing a critical role in the system's functionality. The following are the key components:

Barrel

The barrel is the main body of the pig launcher, where the pig is inserted before it is launched into the pipeline. It is designed to withstand high pressures and is often made of steel to ensure durability.

Closure Door

The closure door is used to insert the pig into the launcher. It is designed to be leak-proof and withstand the internal pressure of the system. Quick-opening closures are often used to allow for easy insertion and removal of pigs.

Isolation Valve

The isolation valve separates the pig launcher from the main pipeline. It prevents fluid from entering the barrel during pig loading or unloading. The valve must be carefully operated to avoid sudden pressure changes.

Kicker Line

The kicker line is responsible for diverting flow from the main pipeline into the launcher to push the pig forward. It provides the necessary force to move the pig from the launcher into the pipeline.

Pig Signaller

The pig signaller provides a visual or electronic signal to indicate when the pig has been launched. It helps operators track the pig's movement within the pipeline.

Drain

The drain is used to remove any residual liquid or gas from the launcher before opening the closure door. It helps ensure safety and prevents accidental spills.

Pressure Indicator

The pressure indicator monitors the internal pressure within the pig launcher. It is essential for ensuring safe operation and preventing over-pressurisation.

PSV & Venting System

The pressure safety valve (PSV) and venting system release excess pressure to prevent potential hazards. The venting system allows gases to be safely expelled during pigging operations.

HOW A PIG LAUNCHER WORKS

The operation of a pig launcher follows a systematic process:

Step 1: Loading the Pig
The pipeline is depressurised, and the closure door is opened. The pig is inserted into the barrel of the launcher. The closure door is securely sealed to prevent leakage.

Step 2: Pressurisation and Isolation
The isolation valve is closed to separate the launcher from the pipeline. The pressure inside the launcher is gradually increased to match that of the pipeline.

Step 3: Pig Launching
The kicker line is opened, allowing pressurised flow to enter the launcher. The fluid pushes the pig from the launcher into the pipeline. The pig signaller confirms when the pig has been successfully launched.

Step 4: Pigging Process
The pig moves through the pipeline, performing its designated function. The movement of the pig is tracked using sensors or pig signallers.

Step 5: Pig Receiving
The pig reaches the receiver, where it is captured and removed from the pipeline. The receiver is depressurised, and the pig is retrieved for inspection or replacement.

Types of Pigs Used in a Pig Launcher
Various types of pigs can be launched depending on the operational requirements. Common types include:

- Cleaning Pigs, used to remove debris, dirt, and scale from the pipeline.
- Inspection Pigs (Intelligent Pigs), equipped with sensors to detect corrosion, cracks, or other structural defects.
- Sealing Pigs, used for separating different products within a pipeline or for hydrostatic testing.
- Foam Pigs, lightweight pigs used for cleaning and dewatering pipelines.

IMPORTANCE OF PIG LAUNCHERS

Pig launchers play a vital role in the maintenance and efficiency of pipelines. Their benefits include:

- Regular pigging removes contaminants, minimising the risk of blockages and maintaining flow efficiency.
- Inspection pigs help detect corrosion early, preventing pipeline failures.
- Sealing pigs prevent mixing of different products in multi-product pipelines.
- Pigging ensures pipelines remain free from obstructions, reducing the risk of hazardous incidents.
- Regular pigging reduces maintenance costs by preventing expensive repairs due to pipeline failures.

SAFETY CONSIDERATIONS

Since pig launchers operate under high pressure, safety measures are crucial to prevent accidents. Key safety guidelines include:

- Avoid sudden pressure changes when launching or retrieving a pig.
- Operators should wear safety gear, including helmets, gloves, and eye protection.
- Strict adherence to standard pigging procedures minimises risks.
- Continuous monitoring helps prevent over-pressurisation and equipment failure.
- Ensure the pig launcher and all its components are in good condition before use.

CONCLUSION

Pig launchers are essential components in modern pipeline systems, facilitating maintenance, inspection, and operational efficiency. Their role in cleaning, monitoring, and ensuring the structural integrity of pipelines cannot be overstated. Understanding the design, functionality, and safety considerations of pig launchers is crucial for anyone involved in pipeline operations. By implementing a well-structured pigging system, companies can significantly improve pipeline reliability, reduce maintenance costs, and ensure long-term operational success.